MNRAS 000, 1–13 (0000) Preprint 12 October 2026 Compiled using MNRAS LATEX style file v3.2

A masked-line ablation audit of a LightGBM F/G/K temperature-class classifier for Gaia-ESO UVES spectra: what survives, and a train–test scale mismatch

Tirthesh Jani[1]⋆
[1] *Lakehead University, Barrie, Ontario, Canada*

Accepted XXX. Received YYY; in original form ZZZ

ABSTRACT

We audit a LightGBM classifier that assigns Gaia-ESO FLAMES-UVES U580 spectra (4800 to 6800 Å) to three effective-temperature classes labelled F, G and K (held-out macro-F1 0.926, $n = 456$). For line sets fixed in advance we interpolate across the covered bins, score the masked spectra with the unmodified model, and compare the per-class recall change with a class-matched null of 5000 bin-matched random windows, with flip counts and an exact McNemar test. Two dependencies survive: masking the Balmer lines lowers F recall by −0.840 (68 of 81 rows lost) and masking Mg B lowers G recall by −0.257 (59 of 230 lost), and the Mg B effect is stable under a constant fill. K recall does not fall under any of the five line sets (at most 3 of 145 rows lost), nor under the 100 bins with the largest K attribution under interpolation; a constant fill over those bins changes K recall by −0.166, so the audit can register a K dependence. The K class is 72.8 percent giants and F and G are almost all dwarfs, so "K versus G" is partly "giant versus dwarf". Polynomial re-normalisation of the test spectra lowers G recall from 0.965 to 0.148; a uniform rescaling by 1.09 reproduces the drop and retraining on re-normalised spectra restores macro-F1 to 0.915, so the collapse is a train–test scale mismatch rather than a continuum shortcut. Cross-validation grouped by survey field estimates cluster leakage at 0.006 in macro-F1, within one fold-to-fold standard deviation.

Key words: Machine Learning – Data Methods – stars: fundamental parameters – techniques: spectroscopic – model interpretability – Gaia-ESO Survey

1 INTRODUCTION

The Morgan-Keenan (MK) system organises stellar spectra by temperature and luminosity using a small set of absorption-line diagnostics: Balmer lines in hot and intermediate stars, Mg B, Fe I and Na D in cooler dwarfs and giants, and molecular bands at the cool end (Gray & Corbally 2009). Machine-learning classifiers now assign MK-like or label-equivalent classes at survey scale, from data-driven label transfer (Ness et al. 2015) and deep networks (Fabbro et al. 2018) to tree ensembles (Li et al. 2019), and invertible networks for parameter inference (Candebat et al. 2024). A classifier with high macro-F1 may rely on the lines a spectroscopist would read, or on other structure in the input that correlates with the label. This paper asks which dependencies of one such classifier survive a controlled intervention, and where the intervention itself misleads.

Intervention and attribution. Attribution methods such as permutation importance, saliency and SHAP rank inputs by how the model uses them. The distinction between "correlational" attribution and "interventional" ablation is less sharp than it is often drawn. Sliding-window occlusion is the same operation as masked-line ablation with a different window. Permutation importance also intervenes on inputs, and TreeSHAP has an interventional form (Lundberg et al. 2020; Janzing et al. 2020). What distinguishes the audit here is narrower: the line sets are fixed before the test set is scored, the readout is a per-class recall change rather than a global score, and the reference distribution is a class-matched, bin-matched random-window null. The choice of fill value defines the explanation, and feature removal produces off-distribution inputs (Hooker et al. 2019; Covert et al. 2021); we therefore use linear interpolation across the masked bins as the primary fill, report a constant fill as a sensitivity check, and treat a change in prediction as a statement about the model's input–output map rather than about stellar physics. Stellar-spectroscopy work has addressed the related question of which pixels inform which label by design: Ting et al. (2019) fit an emulator of ab initio spectra so that each label acts through its physical features, Xiang et al. (2019) regularise a data-driven model with ab initio gradient spectra, and Leung & Bovy (2019) censor inputs so that each abundance sees only windows that contain its own lines. Those approaches constrain the model; ours probes a model that was trained without constraints. On Gaia-ESO spectra

⋆ E-mail: tirtheshjani@gmail.com; ORCID: 0009-0005-5965-4409

© 0000 The Authors

themselves, Ambrosch et al. (2023) and Nepal et al. (2023) train convolutional networks on GIRAFFE spectra and use network gradients to argue that the inferred labels are read from physical lines, and Ye et al. (2025) explain a Gaia XP carbon-star classifier with SHAP; those are attribution readouts of the kind we use as baselines in Section 3.3, not interventions on a fixed model.

Shortcuts. We use "shortcut" in the sense of Geirhos et al. (2020): a decision rule that performs well on the standard test but fails to transfer to a shifted condition. Operationally, a finding of shortcut learning would require three things: a feature that is predictive in the training distribution, is not part of the diagnostic set specified in advance, and whose removal or perturbation degrades performance under a shifted condition. Dependence on Fe I or Cr I lines is physics, since those lines track temperature, and is not a shortcut under this definition. We are not aware of stellar-spectroscopy work that applies this definition to a trained classifier.

Scope. The classifier is a three-class effective-temperature-bin classifier on the red half of the optical, labelled with MK letters; it does not assign spectroscopic MK types and it has no luminosity-class output (Section 2). We apply the audit to a LightGBM model (Ke et al. 2017) trained on Gaia-ESO DR5.1 FLAMES-UVES U580 spectra (Gilmore et al. 2022; Randich et al. 2022; Sacco et al. 2014; Hourihane et al. 2023). The contributions are: (i) a reproducible per-class ablation with class-matched, bin-matched nulls, row-level flip counts and an exact paired test; (ii) the observation that K-class recall is insensitive to any narrow window, with a positive control showing that a constant fill over the most K-relevant bins does register; (iii) a decomposition of the collapse seen under polynomial re-normalisation into a scale effect and a spread effect, with a retraining experiment; (iv) a report of the luminosity-class confound and a field-grouped leakage estimate; and (v) a negative external cross-check. A deviations-from-plan account is given in Section 3.7.

2 DATA

2.1 Survey, instrument and wavelength window

The audit uses FLAMES-UVES U580 spectra from the Gaia-ESO Survey (Gilmore et al. 2022). UVES is a high-resolution echelle spectrograph at the VLT UT2 (Dekker et al. 2000); the FLAMES fibres feed its red arm only (Pasquini et al. 2002). The U580 setting is recorded on the two-CCD mosaic of that arm: the lower chip covers 4770 to 5770 Å and the upper chip 5832 to 6830 Å, separated by the inter-chip gap. We restrict the audit to 4800 to 6800 Å, which lies inside U580 coverage and avoids mixing U520 and U580 setups. The window contains Hβ at 4861 Å, the Mg B triplet at 5167, 5173 and 5184 Å, the Na D doublet at 5890 and 5896 Å, two Ca I features at 6162 and 6439 Å, and Hα at 6563 Å. Wavelengths are in air, following the GES UVES pipeline (Sacco et al. 2014), and rest wavelengths come from the NIST Atomic Spectra Database (Kramida et al. 2023). Continuum normalisation is inherited from the Gaia-ESO pipeline. The audit side re-derives the continuum only in the normalisation experiments of Sections 4.5 and 4.6.

2.2 Labels

Recommended stellar parameters come from the ESO Science Archive TAP service, table `safcat."GES_DR5_1_V1"` (ESO Phase 3 release DR5.1, archive DOI 10.18727/archive/25), as homogenised by Hourihane et al. (2023); the DR5 analysis of the UVES FGK spectra behind those parameters is described by Smiljanic et al. (2014) and Worley et al. (2024). The query returned 6143 catalogue rows with non-null $T_{\rm eff}$, $\log g$ and [Fe/H] under a `REC_SETUP LIKE '%580%'` filter; cross-matching against the regridded UVES store (0.5 arcsec primary radius, 2 arcsec ambiguity cutoff) matched 3955 spectra. Class labels are $T_{\rm eff}$ bins whose edges, 7300, 6000, 5300 and 3900 K, are rounded to the nearest 100 K from the dwarf-sequence scale of Pecaut & Mamajek (2013): F is [6000, 7300) K, G is [5300, 6000) K and K is [3900, 5300) K. These are therefore effective-temperature-bin classes named with MK letters. Two properties follow. First, the bins are applied to giants as well as dwarfs, so luminosity class is a hidden variable (Section 4.4). Second, the GES parameters are derived by a model-atmosphere analysis of these same spectra (Smiljanic et al. 2014), so the audit asks how well a classifier reproduces a spectroscopic $T_{\rm eff}$ bin and which input regions it uses, not how it performs against an independent classification. The single A-type spectrum was dropped at label construction; UVES targets are FGK by design.

2.3 Quality cuts and sample

We require a median signal-to-noise ratio of at least 20 per pixel of the intermediate regridded store (Section 2.4) over the window and cap post-rebin missing bins at 10 percent. The labelled set holds 3032 spectra: F = 536, G = 1534, K = 962. The 0.70/0.15/0.15 train/validation/test split (fixed random seed) gives 2122, 454 and 456 spectra; the test set has F = 81, G = 230, K = 145. Median $T_{\rm eff}$ is 6184, 5711 and 4844 K for F, G and K. Gaia-ESO targets concentrate on open clusters and calibration fields, so spectra are not spatially independent (Section 3.2).

2.4 Wavelength grid and inter-chip gap

Normalised spectra are rebinned by a factor of 5 from the intermediate regridded store onto 696 bins over 4801 to 6796 Å. The grid is log-uniform with $\Delta \ln \lambda = 5.0 \times 10^{-4}$ per bin, so bin widths run from 2.40 to 3.40 Å (mean 2.87 Å; 0.57 Å before rebinning, which is coarser than the native UVES pixel). The corresponding bin resolving power is about 2000, so line windows in this paper are resolved only as blends (Table 1). The inter-chip gap is kept rather than imputed: a boolean `gap_mask` marks the 22 bins whose centres lie in [5771, 5832] Å. Training sees all bins; the importance traces and the random-window controls exclude the gap bins. In the production feature matrix the gap bins hold real but unreliable flux (mean 0.51, standard deviation 0.51 on the test rows), not imputed constants.

3 METHODS

3.1 Features and classifier

Missing bins are filled with a per-bin median fitted on training rows only. Features are not scaled. The model is LightGBM with `max_depth = 8`, `num_leaves = 63`, `learning_rate = 0.05`, `n_estimators = 500`, `early_stopping_rounds = 50`, `min_child_samples = 20`, `subsample = 0.9`, `colsample_bytree = 0.9`, balanced class weights and `random_state = 42`. The hyperparameters were chosen for tractable TreeSHAP, not tuned. The final model is fitted on the training partition only, with validation log-loss for early stopping (best iteration 120); the test set is not used in fitting.

3.2 Cross-validation

On the train+val partition (2576 rows) we run 5-fold StratifiedKFold and a StratifiedGroupKFold pass over spatial groups, since spectra of the same open cluster or field share abundances and reddening and can leak between folds; grouped cross-validation is the standard remedy for such structure (Roberts et al. 2017). Groups are derived from sky coordinates by DBSCAN with the haversine metric (`eps = 0.1 deg`, `min_samples = 5`); noise points receive unique group identifiers. DBSCAN is run once on the coordinates of all 3032 labelled spectra (train, validation and test; no labels are used), and the resulting group identifiers are then restricted to the 2576 train+val rows that enter the cross-validation. Within those rows there are 1926 groups, of which 1845 are singletons and 81 are multi-row clusters. Clustering the train+val rows alone would give a different grouping (clusters that span the partitions lose members), so the group counts quoted here refer to the grouping the spatial pass actually used. Because DBSCAN with `min_samples = 5` leaves any group of fewer than five neighbours as noise, most rows are singletons under this grouping. A third pass therefore groups rows by the Gaia-ESO field identifier (`GES_FLD`, one open cluster or calibration field per value), read from the same catalogue table and matched to the feature rows by sky position (all 3032 rows within 0.002 arcsec of a catalogue entry, none unmatched). The train+val rows fall into 109 fields of median size 10 rows (largest `GES_MW_15_16`, 158 rows); only 12 rows are singletons. Fold scores are summarised by the mean and the population standard deviation over folds. In every cross-validation pass the held-out part of each fold is also the early-stopping set, so the fold scores are mildly optimistic; the production model uses the separate validation partition for early stopping. The DBSCAN group identifiers are re-derived by `scripts/audit_singletons.py` and are not stored in `features.npz`; the field identifiers are deposited in `artifacts/revision/ges_fld_groups.csv`.

3.3 Attribution baselines

On the validation partition we compute permutation importance (10 repeats, accuracy scoring; Breiman 2001), TreeSHAP (Lundberg & Lee 2017; Lundberg et al. 2020) on a stratified subsample of up to 1000 rows (all 454 validation rows are used), and sliding-window occlusion (50 Å window, 25 Å stride, masked bins set to 1.0, a convention that predates the ablation fills; Zeiler & Fergus 2014). Top-20 bin sets are compared with the Jaccard index after removing gap bins. These baselines are exploratory; the ablation below is the test.

3.4 Masked-line ablation

Let $\mathcal{L}$ be a line set, defined as a list of wavelength windows, and $b(\mathcal{L})$ the feature bins whose centres fall in those windows. Table 1 gives the windows, widths and bin counts, together with the other catalogued lines inside each window. For each (line set, class k) pair we compute the change in recall on the test rows of true class k when $b(\mathcal{L})$ is replaced by a fill:

$$\Delta A_k^{(\mathcal{L})} = A_k^{(\mathcal{L}\,\mathrm{masked})} - A_k^{(\mathrm{baseline})}, \tag{1}$$

with a 95 percent percentile bootstrap interval from 2000 resamples of the test rows. The primary fill is linear interpolation across each masked run from the nearest unmasked bins of the same spectrum. The sensitivity fill sets the masked bins to the median of the training matrix outside the gap under the same continuum convention (0.9168 for the production features). Both leave the model and the unmasked bins untouched, but neither is on the data manifold; the effect sizes are statements about this model's response to this edit.

Three paired readouts accompany ΔA_k. The row-level flip counts are the number of class-k rows that move from correct to incorrect (lost) and from incorrect to correct (gained). The exact two-sided McNemar test (McNemar 1947) is applied to those discordant pairs. $\Delta\bar{P}_{\mathrm{true}}$ is the mean change in the predicted probability of the true class, a continuous effect that does not depend on a decision threshold. We also report the one-sided exact Clopper–Pearson 95 percent upper bound on the loss rate (lost rows over class size) (Clopper & Pearson 1934).

The reference distribution is a class-matched null. For each pair we draw 5000 random windows whose total bin count equals $|b(\mathcal{L})|$, constructed from non-overlapping windows that avoid every catalogued diagnostic window and the gap, mask them in the same way, and record the change in class-k recall. The Monte Carlo p-value is $p_{\mathrm{MC}} = (b+1)/(B+1)$, where b counts random windows at least as negative as the observed change and B is the number of windows drawn; the correction keeps p above zero (Phipson & Smyth 2010). It is a valid, slightly conservative Monte Carlo p-value, and its floor is $1/(B+1) = 2.0 \times 10^{-4}$. It tests whether a line window is unusual among windows of the same width; it does not test whether the effect differs from zero, which the interval and the McNemar test address. Line windows and random windows are not exchangeable in the permutation sense, so we do not call the test a permutation test.

The gate, whose line sets were fixed before the test set was scored and whose class assignments were frozen in the same step as the first ablation run (Section 3.7), is: at least two of the three headline pairs (H Balmer, F), (Mg B, G) and (Mg B, K) satisfy a bootstrap interval upper bound below zero and $p_{\mathrm{MC}} \leq 0.01/3$ (family-wise $\alpha = 0.01$, Bonferroni over three pairs; the decision log records the per-pair threshold as 0.01 and the division by three was applied in the driver script, and since both headline p-values sit at the floor the choice does not change the outcome). All other pairs, including (Na D, K), (Ca I, K) and the post-hoc Fe I/Cr I set, are descriptive.

We apply one standard to every K pair: the interval, the flip counts and the McNemar p. For orientation, we mark a zone of ± 0.025 in ΔA; this zone was chosen after the data were seen (Section 3.7) and is used only to describe interval width, not as an equivalence test in the sense of Schuirmann (1987) and Lakens (2017).

As a positive control for the K-class result, one further run masks all five line sets jointly (56 bins) and the 20, 50 and 100 bins with the largest mean |SHAP| for class K on the validation partition (Section 3.3; no test row enters the selection), under both fills and the same class-matched null. Because every tested set is excluded from the random windows, the null in that run avoids 151 bins against 78 in the main run; the five catalogued sets reproduce their deposited recall changes and flip counts exactly in it, and only 6 of their 15 Monte Carlo p-values move, by at most 0.078. The SHAP-ranked sets are post hoc.

Equivalent widths of the Mg B triplet (Section 4.3) are measured against a local continuum within ± 15 Å of each line with a line half-width of ± 3 Å.

3.5 Normalisation experiments

Two experiments separate scale from spread. In the first, the fixed production model scores test spectra after a transformation of the off-gap bins: (a) sigma-clipped Legendre renormalisation of order 5 (clip 3.0 σ, 5 iterations; "polynomial_n5"; the fit is over all bins, and the low gap-bin values are removed by the clipping), with and without restoring the production values in the gap bins; (b) rescaling each row to the common test median (class spread removed, scale kept); (c) multiplying every row by 1.09, and by 1.095 (the ratio of the polynomial and production global medians); (d) swapping the G and K median levels. Gap bins keep their production values under (b) to (d). A one-feature logistic regression on the per-row off-gap median measures how much class information the level carries. In the second experiment LightGBM is retrained with the production hyperparameters on the same train/validation/test partition under three feature matrices: the production features, polynomial_n5, and per-row median normalisation. The ablation of Mg B is repeated on each retrained model (constant fill at the median of that test matrix, which is the deposited convention this experiment was first run under, rather than the training median of Section 3.4; class-matched null, 500 windows, 500 bootstrap resamples). The production retrain reproduces the deposited model exactly, which fixes the sanity check, and the retraining script reproduces the 5-fold StratifiedKFold estimate of Section 3.2 (macro-F1 0.913 with population standard deviation 0.012 over the same five folds; the script prints the sample standard deviation, 0.013).

3.6 Luminosity and boundary distance

Luminosity class is taken from the GES surface gravity: dwarfs have $\log g > 3.5$. Distance to a class boundary is the distance in $T_{\rm eff}$ to the nearest edge of the row's own $T_{\rm eff}$ bin (the deposited `boundary_distance_k`); an interior variant that measures the distance only to the 5300 and 6000 K boundaries shared by the three classes is reported where it differs. We report class composition, per-luminosity accuracy, and the stratified ablation splits for rows within 150 K of a boundary against those beyond.

3.7 Deviations from the plan

The analysis followed a dated decision log (`docs/decision_log.md`); the commit hashes cited in an earlier draft are not part of the public repository history, so we cite the log instead. We use "pre-specified" for choices recorded before the relevant data were scored, and not "preregistered": nothing was lodged in an external registry. The deviations were as follows.

(i) *Line sets and assignments.* The line sets were logged on 2026-04-29, before the test set was first scored on 2026-04-30. That log entry named Mg B, Na D and H Balmer as the headline line sets; after the validation-split triangulation, the (line set, class) assignments were frozen on 2026-04-30, about eight hours after the test set was first scored, in the same step as the first ablation run (the log does not separate the two). In that step (Na D, K) moved from headline to pivot status, (Ca I, K) from supporting to pivot status, (H Balmer, F) replaced the (H Balmer, A) pair that the dropped A class made void, and (Mg B, K) became a headline pair.

(ii) *What the gate licenses.* The gate passes when at least two of three headline pairs reject the null. Because (Mg B, K) is one of the three, a pass says nothing about that pair; the K result is a failure to reject, and we do not read it as confirmation of a hypothesis.

(iii) *Fill value.* The planned constant fill was 1.0. A sensitivity run shifted the headline ΔA by up to 0.039, above the trigger threshold of 0.02, so the deposited run used the median of the test matrix outside the gap (0.9158), not the training median (0.9168). In this revision the primary fill is linear interpolation and the constant fill uses the training median.

(iv) *Indifference zone.* The ± 0.025 zone was set on 2026-05-16, after the ablation results of 2026-04-30 and with the (Mg B, G) effect in view. It is descriptive only.

(v) *Post-hoc line set.* The Fe I/Cr I set was built after the SHAP analysis and is not part of the gate.

(vi) *Analyses added in revision.* The class-matched null, the bin-matched windows, 5000 random windows, the interpolation fill, the McNemar and probability readouts, the scale decomposition, the retraining, the luminosity and boundary stratification, and the corrected template cross-check were all run after an internal review of the first draft; the field-grouped cross-validation and the K-class positive control were added in a second internal review round. They are exploratory.

(vii) *External cross-check.* The Pickles cross-check had an agreement gate of 0.55 with at least 100 compared rows, set on the day of its first run in place of a planned 0.70. It was not met under any continuum convention (Appendix A).

4 RESULTS

4.1 Classifier performance and attribution

On the 456 test spectra the classifier reaches macro-F1 0.926 and accuracy 0.934 (Table 2). Off-diagonal mass sits at adjacent boundaries (Figure B2): F–G confusion in either di-

[ht]

Table 1. Line sets used in the ablation: air wavelength windows, total mask width, number of feature bins covered, and the other catalogued lines inside each window (other species and same-species lines that are not targets). The Mg B window also holds Fe I lines, so "Mg B dependence" means dependence on that 21 Å region. The Fe I/Cr I set was defined after the SHAP analysis and is post hoc. Bin widths vary with wavelength because the grid is log-uniform.

Line set	Window (Å)	Target lines (Å)	Width (Å)	Bins	Other lines inside window (Å)
H Balmer	6542.8–6582.8	6562.80	40	12	Fe I 6546.24; Ti I 6554.22; Ti I 6556.06; Fe I 6569.21; Ca I 6572.78; Fe I 6574.23
	4841.3–4881.3	4861.33	40	17	Fe I 4859.74; Fe I 4871.32; Fe I 4872.14; Fe I 4878.21
total			80	29	
Mg b	5165.0–5186.0	5167.32, 5172.68, 5183.60	21	8	Fe I 5167.49; Fe I 5168.90; Fe II 5169.03; Fe I 5171.60; Ti I 5173.74
Na D	5887.0–5898.0	5889.95, 5895.92	11	4	Ni I 5892.88
Ca I	6160.0–6164.0	6162.17	4	1	Na I 6160.75; Ca I 6161.30; Ca I 6163.75
	6437.0–6441.0	6439.08	4	1	Eu II 6437.64
total			8	2	
Fe I/Cr I	5201.0–5215.0	5206.04, 5208.42	14	6	Fe I 5202.34; Cr I 5204.51; Fe I 5204.58; Y II 5205.73; Fe I 5208.59; Ti I 5210.39
	5264.0–5274.0	5269.54	10	3	Fe II 5264.81; Ca I 5265.56; Fe I 5266.56; Ca I 5270.27; Fe I 5270.36; Fe I 5273.17
	5340.0–5350.0	5345.80	10	4	Fe I 5341.03; Co I 5342.70; Cr I 5348.31
total			34	13	

rection is 3.5 percent of test rows and G–K confusion 2.9 percent, with 1 F–K row (0.22 percent). Five-fold Stratified-KFold gives macro-F1 0.913 ($\pm$0.012) and the spatial pass 0.903 ($\pm$0.016); the difference of 0.010 lies inside the fold-to-fold spread. Because 95.8 percent of the spatial groups, covering 71.6 percent of train+val rows, are singletons, the spatial pass gives no group stratification for most rows. The pass grouped by survey field, in which only 0.5 percent of rows are singletons, gives 0.906 ($\pm$0.018; folds of 373 to 767 rows, since the Milky Way fields are large, with fold scores from 0.878 to 0.929), which is 0.006 below the plain estimate and +0.004 above the spatial pass; the test score is 1.1 field-CV standard deviations above the field mean. Leakage between field-mates therefore accounts for about 0.006 of macro-F1 on train+val, within one fold-to-fold standard deviation. On the 280 test rows whose $T_{\rm eff}$ lies more than 200 K from the nearest edge of their own $T_{\rm eff}$ bin, accuracy is 0.993 against 0.934 overall ($\Delta = 0.059$, 95 percent interval [0.039, 0.082]); at the 150 K cut used for the stratified ablation (Section 4.4) it is 0.985 on 326 rows.

The permutation–SHAP Jaccard index is 0.481, and occlusion agrees poorly with either (0.111 and 0.111), partly because its 50 Å windows are not comparable with bin-level rankings. The 4 bins in all three top sets lie between 6559 and 6569 Å, in the Hα region. These rankings (Appendix B, Figure B1) indicate which windows may matter; they do not show that the model depends on them.

4.2 Masked-line ablation

Table 3 gives the primary configuration (production continuum, interpolation fill) for all five line sets and three classes; Figure 1 shows the headline and pivot pairs, and the sensitivity table (Table 4) varies the continuum and the fill.

Headline pairs. Masking the Balmer lines changes F recall by -0.840 (95 percent interval [-0.915, -0.761]; 68 of 81 rows lost, 0 gained; McNemar $p = 6.8 \times 10^{-21}$), and masking Mg B changes G recall by -0.257 ([-0.318, -0.203]; 59 of 230 lost, 0 gained; McNemar $p = 3.5 \times 10^{-18}$). Both sit at the Monte Carlo floor, $p_{\rm MC} = 2.0 \times 10^{-4}$: none of 5000 random windows is as damaging. The gate result is PASS: 2 of 3 headline pairs satisfy the criterion. The third, (Mg B, K), does not ($\Delta A_K = +0.014$, interval [-0.013, +0.042], $p_{\rm MC} = 0.994$); that is the expected outcome for a null result, and the gate requires only two of three. Masking the Balmer lines also changes G recall by -0.917 (211 of 230 rows lost), although (H Balmer, G) was not a headline pair.

[ht]

Table 2. Held-out test performance. Macro values average F, G and K without weights. Rows of the confusion matrix are the true class, columns the prediction, in F–G–K order: F = (68, 13, 0), G = (3, 222, 5), K = (1, 8, 136).

Class	$n_{\rm test}$	Precision	Recall	F1
F	81	0.944	0.840	0.889
G	230	0.914	0.965	0.939
K	145	0.965	0.938	0.951
Macro	456	0.941	0.914	0.926

Fill dependence. The size of the Balmer effect depends on the fill. For G rows, ΔA_G is -0.917 with interpolation (211 rows lost, 0 gained) and -0.387 with the constant fill (93 lost, 4 gained). For F rows the number lost is the same (68 and 68) but the destinations differ: 63 go to K and 5 to G with interpolation, and 58 go to G and 10 to K with the constant fill. We therefore read the Balmer result as a firm statement that the model depends on the Balmer region for F and G, and treat its magnitude and the direction of its errors as properties of the edit. The Mg B effect on G is stable across fills: -0.257 with interpolation and -0.213 with the constant fill (50 lost, 1 gained; McNemar $p = 4.6 \times 10^{-14}$).

Direction of the response. With Mg B masked, 41 lost G rows are read as F and 18 as K; of the 59 lost rows, 59 are dwarfs, and their median $T_{\rm eff}$ is 5838 K, beside the F/G boundary at 6000 K. The mean change in the probability of the true class is −0.261 on G rows. Most lost rows therefore move toward F, not toward K, and the loss is concentrated near the class boundaries (Section 4.4). Removing Mg B weakens a temperature indicator and the model answers as a temperature estimator would; this is a statement about the model's response to the edit, not a measurement of how the model separates G from K.

Polynomial continuum. Under polynomial_n5 the fixed model has baseline accuracy 0.498 (G recall 0.148), against 0.934 on the production features, so the ablation deltas there describe an already degraded model. They are smaller but still resolved for G: Mg B gives −0.048 with interpolation and −0.057 with the constant fill (McNemar $p = 0.0074$ and 9.8×10^{-4}), and the Balmer lines give −0.728 on F. All 2000-resample intervals, flip counts and p-values for the 15 pairs under the four configurations are in `artifacts/revision/ablation_recalibrated.csv`.

4.3 The K class responds to no narrow window

K-class recall barely changes under any of the five line sets (Table 4). Counting rows in the primary configuration, no line set loses more than 3 of the 145 K rows: Fe I/Cr I loses 3 and gains 0 (McNemar $p = 0.250$), (Mg B, K) loses 1 and gains 3 ($p = 0.625$), (Na D, K) loses 1 and gains 0 ($p = 1.000$), and (Ca I, K) loses 0 and gains 0. The one-sided exact 95 percent upper bound on the loss rate is at most 0.053 for any line set, 0.032 for Mg B and Na D, and 0.020 for Ca I. The largest decrease in K recall is 0.021. K recall can also rise: masking the Balmer lines gains 8 rows ($\Delta A_K = +0.055$, McNemar $p = 0.0078$). This is the same temperature response as in Section 4.2: a mask that makes a star look cooler can only add K rows, and the gain is not reliance of K on the masked region.

Why the Monte Carlo p is not the K evidence. For K the class-matched reference distribution is concentrated at zero: only 6 of 5000 random 4-bin windows lower K recall by as much as one row, so one lost row in (Na D, K) ($\Delta A_K = -0.007$, McNemar $p = 1.000$) already gives $p_{\rm MC} = 0.0014$. For (Fe I/Cr I, K) none of the random windows loses as many as 3 K rows (0 at least as extreme), so 3 lost rows sit at the floor, $p_{\rm MC} = 2.0 \times 10^{-4}$. These values say that the window is unusual among windows of its width, which is a statement about how rarely any window moves K, and not that the effect differs from zero. We therefore apply one standard to every K pair, namely flip counts, the exact McNemar test and the exact upper bound, and we do not call (Na D, K) or (Fe I/Cr I, K) effects; the Fe I/Cr I result is suggestive at most.

For (Mg B, K) the change is +0.014 with interpolation (interval [−0.013, +0.042]) and 0.000 with the constant fill (1 lost, 1 gained). Under polynomial_n5 it is −0.014 with interpolation (3 lost, 1 gained; McNemar $p = 0.625$) and −0.034 with the constant fill (6 and 1; $p = 0.125$). The McNemar test rejects in neither case, and the model is already degraded there. For (Ca I, K) under polynomial_n5 the change is −0.007 with $p_{\rm MC} = 0.056$. The defensible statement is that K predictions barely respond to any of the five line sets we masked (8 to 80 Å total width). It is not evidence for a particular alternative route, and an upper bound is not a measurement of zero.

The Mg B equivalent width on K spectra is not small: the median is 4.17 Å against 3.53 Å on G and 2.25 Å on F (K minus G 0.65 Å; KS $p = 2.6 \times 10^{-7}$). This rules out the explanation that the K Mg B signal is too weak to matter, but Mg B wings are a gravity indicator and the K sample is giant-dominated, so the comparison is confounded by luminosity (Section 4.4).

Positive control. Narrow windows are not the only masks we tried (Table 5). Masking all five line sets jointly (56 bins) leaves K recall unchanged or higher under both fills (+0.055 with interpolation, +0.014 with the constant fill). Masking the 100 bins with the largest validation-set mean |SHAP| for K (14 percent of the spectrum in 61 runs, carrying 86 percent of the total K attribution) raises K recall by +0.062 with interpolation (9 rows gained, 0 lost) but lowers it by −0.166 with the constant fill (25 of 145 rows lost, all to G, 1 gained; McNemar $p = 8.0 \times 10^{-7}$; upper bound on the loss rate 0.232), and the mean probability of the true class changes by −0.339. The constant fill already moves that probability at 20 and 50 bins (−0.051 and −0.127) before any row changes class. The two fills disagree because interpolating across the Balmer cores and the other K-ranked runs makes a spectrum look cooler: under the top-100 mask with interpolation, 62 of the 67 lost F rows and all 214 lost G rows are relabelled K. Two conclusions follow. The ablation can register a K dependence when enough K-relevant bins are removed with a constant fill, so the null results for the five line sets are not an artefact of a readout that cannot see K. And with the interpolation fill no mask we tried lowers K recall, so "K recall does not respond" must be read as "does not fall". Interpolation does not push every spectrum toward the cooler class: under the Mg B mask most lost G rows move to F, the hotter class (Section 4.2). What holds for every mask we tried is narrower. Interpolating across the Balmer cores and the SHAP-ranked runs removes features that are stronger in hotter stars, so rows move toward K; interpolating across Mg B removes a feature that is stronger in cooler stars, so rows move away from K, but only 1 K row leaves, because the K giants sit far from the 5300 K boundary. K is the sink for the first kind of mask and is insulated by boundary distance from the second.

4.4 The luminosity-class confound


The K class is mostly giants and the F and G classes are almost all dwarfs (Table 6, Figure 2). In the full sample 97.9 percent of F rows, 98.2 percent of G rows and 27.2 percent of K rows have $\log g > 3.5$, with median $\log g$ of 4.01, 4.23 and 2.68. On the test set the model scores 0.991 on K giants ($n = 107$) and 0.789 on K dwarfs ($n = 38$); it scores 0.969 on G dwarfs ($n = 229$) and 0.000 on G giants ($n = 1$). The 5 G rows predicted K include 4 dwarfs; their median $\log g$ is 3.78 and median $T_{\rm eff}$ 5345 K. "K against G" is therefore partly "giant against dwarf". The labels are $T_{\rm eff}$ bins on a dwarf scale, so "K" here means a $T_{\rm eff}$ bin that is mostly populated by red giants.

K rows also lie far from the class boundaries: the median distance to the nearest edge of the row's own $T_{\rm eff}$ bin is 433 K for K against 180 for F and 211 for G, and only 24 of 145 K rows lie within 150 K of an edge. Accuracy within that

[ht]

Table 3. Masked-line ablation of the fixed production classifier on the 456 test spectra. Production continuum, linear-interpolation fill, class-matched null of 5000 bin-matched random windows, 2000 bootstrap resamples. ΔA is the change in class recall, with the 95 percent bootstrap interval; "Flips" are rows lost and gained; p_{McN} is the exact McNemar p; $\Delta\bar{P}_{\mathrm{true}}$ is the mean change in the probability of the true class; $p_{\mathrm{MC}} = (b+1)/(B+1)$ against the random-window null. The three headline pairs are (H Balmer, F), (Mg B, G) and (Mg B, K); (Na D, K) and (Ca I, K) are pivot pairs, and all other rows are descriptive. The Fe I/Cr I set is post hoc.

Line set	Class	n	ΔA	95% CI	Flips (lost/gained)	p_{McN}	$\Delta\bar{P}_{\mathrm{true}}$	p_{MC}
H Balmer	F	81	−0.840	[−0.915, −0.761]	68/0	6.8×10^{-21}	−0.801	2.0×10^{-4}
	G	230	−0.917	[−0.952, −0.882]	211/0	6.1×10^{-64}	−0.793	2.0×10^{-4}
	K	145	+0.055	[+0.021, +0.095]	0/8	0.0078	+0.055	1.000
Mg B	F	81	+0.099	[+0.039, +0.167]	0/8	0.0078	+0.078	1.000
	G	230	−0.257	[−0.318, −0.203]	59/0	3.5×10^{-18}	−0.261	2.0×10^{-4}
	K	145	+0.014	[−0.013, +0.042]	1/3	0.625	+0.015	0.994
Na D	F	81	0.000	[+0.000, +0.000]	0/0	1.000	+0.002	1.000
	G	230	+0.004	[+0.000, +0.014]	0/1	1.000	+0.001	0.994
	K	145	−0.007	[−0.023, +0.000]	1/0	1.000	−0.003	0.0014
Ca I	F	81	0.000	[+0.000, +0.000]	0/0	1.000	0.000	1.000
	G	230	0.000	[+0.000, +0.000]	0/0	1.000	0.000	0.974
	K	145	0.000	[+0.000, +0.000]	0/0	1.000	0.000	0.999
Fe I/Cr I	F	81	+0.012	[+0.000, +0.041]	0/1	1.000	+0.009	1.000
	G	230	−0.009	[−0.027, +0.008]	3/1	0.625	−0.006	0.262
	K	145	−0.021	[−0.047, +0.000]	3/0	0.250	−0.016	2.0×10^{-4}



[ht]

Figure 1. Change in class recall $\Delta A_k^{(\mathcal{L})}$ for the headline (solid) and pivot (hatched) pairs in the primary configuration (production continuum, interpolation fill). Error bars are 95 percent bootstrap intervals (2000 resamples); each bar is annotated with ΔA and the Monte Carlo p-value against 5000 class-matched, bin-matched random windows (floor 2.0×10^{-4}). The K bars are small but not exactly zero in rows (Section 4.3); the values match Table 3.

[ht]

Table 4. K-class ΔA_K (rows lost/gained in brackets) for each line set under the 2 × 2 design: production or polynomial_n5 continuum, each with interpolation (primary) or constant fill. The constant fill is the median of the training matrix outside the gap under the same continuum (0.9168 for production, 1.0034 for polynomial_n5).

Line set	Prod., interp.	Prod., constant	Poly., interp.	Poly., constant
H Balmer	+0.055 (0/8)	+0.028 (3/7)	+0.076 (0/11)	+0.076 (0/11)
Mg b	+0.014 (1/3)	0.000 (1/1)	−0.014 (3/1)	−0.034 (6/1)
Na D	−0.007 (1/0)	−0.007 (1/0)	+0.007 (0/1)	+0.007 (0/1)
Ca I	0.000 (0/0)	0.000 (0/0)	−0.007 (1/0)	−0.007 (1/0)
Fe I/Cr I	−0.021 (3/0)	−0.021 (3/0)	−0.014 (2/0)	−0.028 (4/0)

[ht]

Table 5. K-class positive control: ΔA_K for the joint mask of all five line sets and for the 20, 50 and 100 bins with the largest validation-set mean |SHAP| for class K, under the interpolation and constant fills (production continuum, class-matched null of 5000 bin-matched windows, 2000 bootstrap resamples). "Upper bound" is the one-sided exact 95 percent Clopper–Pearson bound on the loss rate. The SHAP-ranked sets are post hoc; 27 of the 100 bins lie inside the catalogued windows.

Mask	Fill	Bins	ΔA_K [95% CI]	Flips (l/g)	p_{McN}	Upper bound	$\Delta\bar{P}_{\mathrm{true}}$
All five sets jointly	interpolation	56	+0.055 [+0.020, +0.093]	0/8	0.0078	0.020	+0.054
	constant	56	+0.014 [−0.027, +0.054]	4/6	0.754	0.062	−0.054
Top-20 K |SHAP| bins	interpolation	20	+0.055 [+0.021, +0.096]	0/8	0.0078	0.020	+0.037
	constant	20	+0.021 [−0.020, +0.063]	3/6	0.508	0.053	−0.051
Top-50 K |SHAP| bins	interpolation	50	+0.041 [+0.007, +0.080]	1/7	0.070	0.032	+0.034
	constant	50	0.000 [−0.043, +0.041]	5/5	1.000	0.071	−0.127
Top-100 K |SHAP| bins	interpolation	100	+0.062 [+0.026, +0.106]	0/9	0.0039	0.020	+0.055
	constant	100	−0.166 [−0.232, −0.106]	25/1	8.0×10^{-7}	0.232	−0.339

distance is 0.667 for K and beyond it 0.992. Measuring the distance only to the shared 5300 and 6000 K boundaries gives a K median of 486 K and 22 rows within 150 K; the F and G values do not change. A push toward a hotter or cooler prediction, which is what masking a line does to a temperature estimator, rarely carries a K row across a boundary, which limits what an unchanged K recall can mean.

Table B1 (Appendix B) splits the principal pairs by luminosity class and by boundary distance. For F and G the luminosity split is uninformative, since only three F rows and one G row are giants. Under Mg b masking, 59 of the 59 lost G rows are dwarfs, and the loss is concentrated near the boundaries: $\Delta A_G = -0.444$ for the 72 G rows within 150 K of an edge of their bin against −0.171 beyond it, and 32 of the lost rows lie within that distance. For K, every row that changes class is a dwarf: across the five line sets 3 distinct K rows are lost, 3 of them dwarfs and 2 within 150 K of an edge, while K giants ($n = 107$) lose 0 and gain 0 rows. The K gains under Balmer masking are also dwarfs (8 rows, $\Delta A_K = +0.211$ among the 38 K dwarfs). The apparent insensitivity of the K class is therefore largely the insensitivity of its giants, which never change class under any mask.

4.5 Scale mismatch under polynomial re-normalisation

Re-deriving the continuum of the test rows with a sigma-clipped polynomial lowers G recall from 0.965 to 0.148 and macro-F1 from 0.926 to 0.475, with 126 of 230 G rows moving to K and 70 to F (Table 7). The re-normalisation changes two things at once: it removes the class-dependent level spread, and it lifts the global median level from 0.9158 to 1.0032, about 9.5 percent. Gradient-boosted trees split on absolute thresholds, so a level shift can move every bin across a split. The decomposition with the model held fixed separates the two effects (Table 7, Figure 3).

- Removing the spread while keeping the scale (every row

[ht]




Figure 2. Kiel diagram of the labelled sample coloured by class. The F and G classes lie on the dwarf branch and the K class is dominated by giants; the dwarf cut is $\log g = 3.5$.

[ht]

Table 6. Composition and test accuracy by luminosity class. Dwarfs have $\log g > 3.5$. Fractions are over the full labelled sample; accuracies are on the held-out test rows (counts in brackets).

Class	n	Dwarf (%)	Median $\log g$	Median $T_{\rm eff}$ (K)	Test acc., dwarfs	Test acc., giants
F	536	97.9	4.01	6184	0.859 (78)	0.333 (3)
G	1534	98.2	4.23	5711	0.969 (229)	0.000 (1)
K	962	27.2	2.68	4844	0.789 (38)	0.991 (107)

rescaled to the common test median) costs 0.017 in macro-F1 (to 0.910) and leaves 5 G rows going to K.

- Keeping the spread and shifting the scale (every row multiplied by 1.09) reproduces the collapse: macro-F1 0.550, G recall 0.217, and 127 G rows going to K. The ratio of the global medians, 1.095, gives 0.527 and 133 rows.
- Swapping the G and K median levels costs 0.031 and raises G→K to 13.
- Restoring the production values of the gap bins after re-normalisation changes macro-F1 by less than 0.005 (0.472 against 0.475), so the gap bins do not carry the effect.

The level itself holds weak class information. A one-feature logistic regression on the per-row off-gap median reaches accuracy 0.386 (balanced accuracy 0.475) on the test set, with ROC AUC 0.69 for G against K and 0.66 for F against G. The per-class median of the row medians is 0.929 (F), 0.918 (G) and 0.902 (K) under the production normalisation, a spread of 2.6 percentage points before rounding, with KS p of 8.4×10^{-5} (F–G), 2.1×10^{-8} (G–K) and 1.0×10^{-11} (F–K). After the polynomial fit the medians are 1.001, 1.003 and 1.006 (a spread of 0.5 points, with the order reversed), and the KS p are 1.8×10^{-5}, 6.0×10^{-9} and 9.0×10^{-18}. The level carries real but weak class information, but a model that read only the level could not reach G recall of 0.965, and after re-normalisation all three class medians lie above the production F median, so a model that read the level would be expected to move G toward F rather than K. We conclude that the polynomial collapse is a train–test scale mismatch: the model has not seen the scale of the re-normalised inputs. This is brittleness to a normalisation convention, which is a failure to transfer to a shifted condition. We do not identify a specific unintended feature the model relies on, and we therefore do not call it shortcut learning.

4.6 Retraining on re-normalised spectra

We ran the retraining experiment that tests whether the K result depends on the continuum convention (Table 8). The production retrain reproduces the deposited model exactly (macro-F1 difference 0.000, identical confusion matrix, best iteration 120). Retrained on polynomial_n5 features the model reaches macro-F1 0.915 and on row-median-normalised features 0.915, a loss of 0.011 and 0.011 against the production 0.926. This is within the fold-to-fold spread of 5-fold cross-validation on the production matrix (0.913 with population standard deviation 0.012; Section 3.2). The classifier loses about a hundredth of macro-F1 without the level, so the level is not what carries performance. In every retrained model the (Mg B, K) change is null or slightly positive (0.000, +0.014, +0.021, +0.014 for the four matrices), while (Mg B, G) is clearly negative (−0.213, −0.152, −0.152, −0.200). The change in K recall seen when the fixed model scores polynomial-normalised inputs (−0.014 with interpolation and −0.034 with the constant fill; Table 4) is therefore a response of a model scored far from its training conditions (baseline accuracy 0.498), not a property of the K class. The retraining was first planned as future work; because the same rows train, validate and test, it does not invalidate the split. The Mg B results do not depend on the normalisation convention; Section 4.7 varies the training choices instead.

4.7 Robustness of the (Mg B, K) effect to training choices

Two further retrains were run on the production features with the deposited constant fill. With uniform class weights the model reaches macro-F1 0.925 and the (Mg B, K) change is +0.014. Across a 3×3 grid of `max_depth` $\in \{6, 8, 10\}$ and `num_leaves` $\in \{31, 63, 127\}$ (9 cells) the largest absolute change is 0.021. The grid does not vary the learning rate, the column subsampling, the objective or the regularisation, so this is a statement about those nine cells and not about gradient-boosted trees in general.

5 DISCUSSION


What the audit adds. A fixed, pre-specified list of line sets, a per-class readout and a class-matched, bin-matched null make the answer to "does this classifier depend on this window for this class" reproducible, and the flip counts and McNemar test make the K-class statement honest about how few rows move. The method is an operation on the input domain of a fixed model and does not depend on the architecture. It does not separate a physical dependence from a response to an edited input, since masking and interpolation can leave the data manifold (Hooker et al. 2019; Covert et al. 2021), and it measures reliance on a window, not the causal effect of a stellar property. The prior-art approaches that build the dependence structure into the model (Ting et al. 2019; Xiang et al. 2019; Leung & Bovy 2019) answer a different question: how to constrain a model, where we probe an unconstrained one.

Attribution baselines and ablation. The three baselines of Section 3.3 point at the Balmer and Mg B regions and disagree elsewhere. A ranking says where the model looks; only the intervention says whether the prediction changes when the region is edited, and K-class insensitivity is a property of that response. The scale mismatch is not an attribution result at all: it appears when the per-class level and the global scale of the inputs are examined directly.

[ht]

Table 7. The fixed production model scored on transformed test spectra. Recall per class, macro-F1 and the number of G rows predicted K, with the median row level in the last column. "Spread removed" rescales each row to the common test median; "G/K swap" exchanges the two class median levels.

Transformation	R_F	R_G	R_K	macro-F1	G→K	Median level
Production	0.840	0.965	0.938	0.926	5	0.916
Polynomial_n5	0.728	0.148	0.924	0.475	126	1.003
Polynomial_n5, gap restored	0.728	0.143	0.924	0.472	126	1.003
Spread removed, scale kept	0.864	0.930	0.931	0.910	5	0.916
Every row × 1.09	0.790	0.217	0.972	0.550	127	0.998
Every row × 1.095	0.778	0.187	0.966	0.527	133	1.003
G/K swap	0.840	0.900	0.945	0.895	13	0.911



[ht]

Figure 3. Per-row median of normalised flux outside the inter-chip gap by class on the test set, under the production normalisation (left) and after the polynomial re-normalisation (right). Class medians are given in Section 4.5; the numbers come from the same artifact as Table 7.

[ht]

Table 8. LightGBM retrained with the production hyperparameters on each feature matrix (same train/validation/test rows). Recall per class, macro-F1, G rows predicted K, and the Mg B ablation on K and G (constant fill at the test-matrix median, the deposited convention of this experiment, whereas Tables 3 and 4 use the training median; class-matched null, 500 windows, 500 bootstrap resamples). Intervals are 95 percent bootstrap intervals.

Features	R_F	R_G	R_K	macro-F1	G→K	ΔA_K (Mg B) [95%] (p_{MC})	ΔA_G (Mg B) [95%] (p_{MC})
Production	0.840	0.965	0.938	0.926	5	0.000 [−0.021, +0.020] (0.896)	−0.213 [−0.268, −0.161] (0.0020)
Polynomial_n5	0.802	0.952	0.966	0.915	4	+0.014 [0.000, +0.036] (1.000)	−0.152 [−0.199, −0.106] (0.0100)
Polynomial_n5, gap restored	0.815	0.943	0.959	0.911	3	+0.021 [0.000, +0.047] (1.000)	−0.152 [−0.198, −0.109] (0.0100)
Row-median	0.852	0.930	0.959	0.915	6	+0.014 [0.000, +0.035] (1.000)	−0.200 [−0.256, −0.146] (0.0020)

The scale mismatch. The earlier reading, that the model used the per-class continuum level as its main G-versus-K discriminator, fails three tests. A uniform rescaling that keeps the spread reproduces the collapse; removing the spread while keeping the scale does not; and retraining without the level costs about a hundredth of macro-F1. That a tree ensemble fails under a uniform rescaling of its inputs is dataset shift in the sense of Quiñonero-Candela et al. (2009), here a deterministic transformation of the inputs that moves their distribution while the physical labelling rule stays fixed: trees split on absolute thresholds, so nothing in the model carries over across a change of scale, and the contribution here is the decomposition, not the phenomenon. The closest stellar-spectroscopy precedents are the mismatch between synthetic training spectra and observed spectra documented by Bialek et al. (2020) and the domain adaptation it motivated (O'Briain et al. 2021); the shift here is smaller and purely multiplicative, which is what makes it easy to miss. For pipeline-normalised spectra the practical lesson is that a tree model scored on a re-normalised matrix, even by a small uniform shift, should be treated as scored on shifted inputs. We recommend reporting the normalisation convention, the global median level, and a uniform-rescaling sensitivity check alongside any such evaluation.

What the K result does and does not say. K recall does not respond to any narrow window: K giants, which are 107 of the 145 K test rows, lose 0 and gain 0 rows under all five masks. The class is giant-dominated, sits far from the class edges, and has many redundant temperature-sensitive features, so a narrow mask removes little that other bins cannot supply. The positive control of Section 4.3 sharpens this in two directions: a constant fill over the 100 most K-relevant bins does lower K recall (by -0.166), so the audit can see a K dependence once enough redundant bins are removed, while the interpolation fill never lowers K recall for any mask we tried, because the masks that remove hotter-star features move rows toward K and the one that removes a cooler-star feature (Mg B) moves almost no K row across the distant 5300 K boundary (Section 4.3). The K statement is therefore conditional on the fill as well as on the width of the mask. We do not infer a shortcut from any of this, and the Fe I/Cr I result is suggestive at most. Comparing with an external parameter-inference network such as that of Candebat et al. (2024) is not informative here, since it is a different task on a different instrument.

6 LIMITATIONS

Labels and luminosity. The classes are $T_{\rm eff}$ bins from parameters derived from the same spectra, on a dwarf scale, and the K class is giant-dominated. The audit tests reproduction of a spectroscopic $T_{\rm eff}$ bin, and no claim about MK classification in the full spectral and luminosity sense follows. Restricting the audit to dwarfs would leave only 38 K test rows.

Resolution and blends. The bins correspond to $R \approx 2000$, so a line window is a blend (Table 1) and the native UVES resolving power is not used by the features. The Mg B window contains Fe I lines, and "Mg B dependence" means dependence on that 21 Å region. The window widths differ by a factor of about ten, from 8 to 80 Å, which is why the nulls are matched in bin count and drawn per class.

Interventions. Interpolation and constant fills are off-distribution edits. The ablation is on a single model, one instrument and one survey, with the GES parameters as labels. Effects based on a few rows do not support claims beyond the sample. The indifference zone was chosen after the data were seen and is descriptive.

Leakage and spatial structure. Because 71.6 percent of train+val rows are in singleton spatial groups, the DBSCAN pass does not constrain cluster leakage; the pass grouped by survey field estimates it at 0.006 of macro-F1 on train+val, within one fold-to-fold standard deviation (Section 3.2). The held-out test split itself is not group-aware, so test rows can share a field with training rows, and the test score should be read with the field-grouped estimate beside it. The DBSCAN group identifiers are re-derived, not deposited; the field identifiers are deposited.

External check. The template cross-check failed its gate and so offers no corroboration (Appendix A).

7 CONCLUSIONS

A LightGBM classifier of three $T_{\rm eff}$-bin classes on Gaia-ESO UVES U580 spectra reaches macro-F1 0.926. Under prespecified masked-line ablation, the F class depends on the Balmer region and the G class on the Mg B region: masking them changes recall by -0.840 and -0.257 (68 and 59 rows lost, 0 gained for Mg B), and rows move as a temperature estimator would move them. The size of the Balmer effect and the destination of its errors depend on the fill; the Mg B effect does not (-0.213 with the constant fill). The K class does not lose recall under any narrow window we tried: no line set loses more than 3 of 145 K rows, and masks that make a star look cooler add K rows. With the interpolation fill no mask, not even the 100 most K-relevant bins, lowers K recall; with a constant fill that mask does (-0.166), so the audit can register a K dependence once one is removed. That is the full content of the K result. Its evidence is flip counts, exact McNemar tests and upper bounds, since the Monte Carlo p-values are near-degenerate for K, and it is a failure to detect a narrow-window dependence in a giant-dominated class, not a finding about what the K class reads instead. The earlier claim of a class-level continuum shortcut does not survive: the collapse under polynomial re-normalisation is a train–test scale mismatch that a uniform 1.09 rescaling reproduces, and retraining on re-normalised spectra restores the classifier and leaves the Mg B effect on K null. For anyone scoring a tree model on re-normalised spectra the caution is practical: report the normalisation convention and the global level, and check sensitivity to a uniform rescaling. The code, model, feature matrix, decision log and every number-producing script are released so that the same probe can be run on other classifiers.

DATA AVAILABILITY

Code is available at `https://github.com/TirtheshJani/ges-uves-mk-audit` under the MIT licence. The trained model (`lgbm_mk.pkl`), the feature matrix (`features.npz`) and the numerical artifacts are deposited at Zenodo (DOI: to be assigned on Zenodo deposit) with the same release tag as the GitHub repository. Reproduction commands, seeds and run times are in `docs/reproducibility_appendix.md`; the provenance of the three local copies of the project is in `docs/folder_provenance.md` and the dated decision log is `docs/decision_log.md`. Every number in this paper is written to `submission/revision_numbers.tex` by `scripts/revision/manuscript_numbers.py`, and `artifacts/revision/manuscript_numbers_index.json` maps each macro to its source artifact; the field identifiers, the field-grouped cross-validation and the K-class positive control are in `artifacts/revision/`. The Gaia-ESO data are public through the ESO Science Archive Facility. The Pickles library is public through the STScI HLSP reference-atlases mirror and is not redistributed.

ACKNOWLEDGEMENTS

This work uses data from the Gaia-ESO Public Spectroscopic Survey (Gilmore et al. 2022; Randich et al. 2022;

Sacco et al. 2014). Based on data products from observations made with ESO Telescopes at the La Silla Paranal Observatory under programme ID 188.B-3002. Based on data obtained from the ESO Science Archive Facility with DOI: `https://doi.org/10.18727/archive/25`. These data products have been processed by the Cambridge Astronomy Survey Unit (CASU) at the Institute of Astronomy, University of Cambridge, and by the FLAMES/UVES reduction team at INAF/Osservatorio Astrofisico di Arcetri. Stellar parameters used for the labels are from Hourihane et al. (2023). Atomic line rest wavelengths are from the NIST Atomic Spectra Database (Kramida et al. 2023). The Pickles library was retrieved from the STScI HLSP reference-atlases mirror. Software includes LightGBM (Ke et al. 2017), SHAP (Lundberg & Lee 2017; Lundberg et al. 2020), scikit-learn (Pedregosa et al. 2011), NumPy (Harris et al. 2020), SciPy (Virtanen et al. 2020), Astropy (Astropy Collaboration et al. 2022), astroquery (Ginsburg et al. 2019) and Matplotlib (Hunter 2007). Large-language-model assistants were used to draft and refactor analysis code, to run internal review passes on earlier drafts and to copy-edit the text; the study design, every analysis and every number in the paper were checked by the author, who takes full responsibility for the content.

REFERENCES

Ambrosch M., Guiglion G., Mikolaitis Š., Chiappini C., Tautvaišienė G., et al., 2023, Astronomy and Astrophysics, 672, A46

Astropy Collaboration et al., 2022, The Astrophysical Journal, 935, 167

Bialek S., Fabbro S., Venn K. A., Kumar N., O'Briain T., Yi K. M., 2020, Monthly Notices of the Royal Astronomical Society, 498, 3817

Breiman L., 2001, Machine Learning, 45, 5

Candebat N., Sacco G. G., Magrini L., Belfiore F., Van der Swaelmen M., Zibetti S., 2024, Astronomy and Astrophysics, 692, A228

Clopper C. J., Pearson E. S., 1934, Biometrika, 26, 404

Covert I., Lundberg S., Lee S.-I., 2021, Journal of Machine Learning Research, 22, 1

Dekker H., D'Odorico S., Kaufer A., Delabre B., Kotzlowski H., 2000, in Iye M., Moorwood A. F., eds, Society of Photo-Optical Instrumentation Engineers (SPIE) Conference Series Vol. 4008, Optical and IR Telescope Instrumentation and Detectors. pp 534–545, doi:10.1117/12.395512

Fabbro S., Venn K. A., O'Briain T., Bialek S., Kielty C. L., Jahandar F., Monty S., 2018, Monthly Notices of the Royal Astronomical Society, 475, 2978

Geirhos R., Jacobsen J.-H., Michaelis C., Zemel R., Brendel W., Bethge M., Wichmann F. A., 2020, Nature Machine Intelligence, 2, 665

Gilmore G., et al., 2022, Astronomy and Astrophysics, 666, A120

Ginsburg A., et al., 2019, The Astronomical Journal, 157, 98

Gray R. O., Corbally C. J., 2009, Stellar Spectral Classification. Princeton Series in Astrophysics, Princeton University Press, Princeton, NJ

Harris C. R., et al., 2020, Nature, 585, 357

Hooker S., Erhan D., Kindermans P.-J., Kim B., 2019, in Advances in Neural Information Processing Systems 32 (NeurIPS 2019). Curran Associates, pp 9737–9748 (`arXiv:1806.10758`)

Hourihane A., et al., 2023, Astronomy and Astrophysics, 676, A129

Hunter J. D., 2007, Computing in Science & Engineering, 9, 90

Janzing D., Minorics L., Blöbaum P., 2020, in Proceedings of the 23rd International Conference on Artificial Intelligence and Statistics (AISTATS 2020). pp 2907–2916 (`arXiv:1910.13413`)

Ke G., Meng Q., Finley T., Wang T., Chen W., Ma W., Ye Q., Liu T.-Y., 2017, in Advances in Neural Information Processing Systems 30 (NeurIPS 2017). Curran Associates, pp 3146–3154

Kramida A., Ralchenko Y., Reader J., NIST ASD Team 2023, NIST Atomic Spectra Database (version 5.11), doi:10.18434/T4W30F, `https://physics.nist.gov/asd`

Lakens D., 2017, Social Psychological and Personality Science, 8, 355

Leung H. W., Bovy J., 2019, Monthly Notices of the Royal Astronomical Society, 483, 3255

Li X.-R., Lin Y.-T., Qiu K.-B., 2019, Research in Astronomy and Astrophysics, 19, 111

Lundberg S. M., Lee S.-I., 2017, in Advances in Neural Information Processing Systems 30 (NeurIPS 2017). Curran Associates, pp 4765–4774 (`arXiv:1705.07874`)

Lundberg S. M., et al., 2020, Nature Machine Intelligence, 2, 56

McNemar Q., 1947, Psychometrika, 12, 153

Nepal S., Guiglion G., de Jong R. S., Valentini M., Chiappini C., et al., 2023, Astronomy and Astrophysics, 671, A61

Ness M., Hogg D. W., Rix H.-W., Ho A. Y. Q., Zasowski G., 2015, The Astrophysical Journal, 808, 16

O'Briain T., Ting Y.-S., Fabbro S., Yi K. M., Venn K. A., Bialek S., 2021, The Astrophysical Journal, 906, 130

Pasquini L., et al., 2002, The Messenger, 110, 1

Pecaut M. J., Mamajek E. E., 2013, The Astrophysical Journal Supplement Series, 208, 9

Pedregosa F., et al., 2011, Journal of Machine Learning Research, 12, 2825

Phipson B., Smyth G. K., 2010, Statistical Applications in Genetics and Molecular Biology, 9, Article 39

Pickles A. J., 1998, Publications of the Astronomical Society of the Pacific, 110, 863

Quiñonero-Candela J., Sugiyama M., Schwaighofer A., Lawrence N. D., eds, 2009, Dataset Shift in Machine Learning. MIT Press, Cambridge, MA

Randich S., et al., 2022, Astronomy and Astrophysics, 666, A121

Roberts D. R., et al., 2017, Ecography, 40, 913

Sacco G. G., et al., 2014, Astronomy and Astrophysics, 565, A113

Schuirmann D. J., 1987, Journal of Pharmacokinetics and Biopharmaceutics, 15, 657

Smiljanic R., Korn A. J., Bergemann M., Frasca A., Magrini L., Masseron T., et al., 2014, Astronomy and Astrophysics, 570, A122

Ting Y.-S., Conroy C., Rix H.-W., Cargile P., 2019, The Astrophysical Journal, 879, 69

Virtanen P., et al., 2020, Nature Methods, 17, 261

Worley C. C., Smiljanic R., Magrini L., Frasca A., Franciosini E., et al., 2024, Astronomy and Astrophysics, 684, A148

Xiang M., et al., 2019, The Astrophysical Journal Supplement Series, 245, 34

Ye S., Cui W.-Y., Li Y.-B., Luo A.-L., Jones H. R. A., 2025, Astronomy and Astrophysics, 697, A107

Zeiler M. D., Fergus R., 2014, in Computer Vision – ECCV 2014. Springer, pp 818–833, doi:10.1007/978-3-319-10590-1_53

APPENDIX A: EXTERNAL CROSS-CHECK AGAINST THE PICKLES LIBRARY: NOT PASSED

No continuum convention reached the pre-specified agreement gate, so the cross-check is reported as a failed external check, not as corroboration. We compared each test spectrum with the 131 spectra of the Pickles UVKLIB library (Pickles 1998) by minimising a unit-variance chi-squared over

[ht]

Table A1. Agreement between the classifier and the spectral type of the best-matching Pickles template under four continuum conventions (gate: agreement ≥ 0.55 and at least 100 compared rows). "Super." is the fraction of best-matching templates that are supergiants. The polynomial_n5 convention gives no F, G or K matches. The last row is an additional variant fitted on a restricted window and is not part of the pre-specified set.

Convention	$n_{\rm FGK}$	Agreement	Macro-F1	Super. (%)
200 Å median filter	448	0.531	0.530	53
50 Å median filter	433	0.416	0.427	17
Polynomial $n = 5$ (sigma-clipped)	0	**n/a**	**n/a**	99
Polynomial $n = 5$, 4700–6900 Å window	387	0.266	0.282	76

bins finite in both spectra, and compared the spectral type of the best template (read from the `COMMENT1` card of its FITS header, which agrees with the embedded map for 131 of 131 templates) with the classifier's prediction; an earlier hand-built index map was mis-assigned from index 17 onward and its results are withdrawn. The gate was agreement of at least 0.55 on at least 100 compared rows. Table A1 gives the result: the best agreement, 0.531 for the 200 Å median-filter normalisation, is below the gate, and for that normalisation 53 percent of best-matching templates are supergiants, a luminosity class essentially absent from the test sample. The polynomial_n5 convention yields no F, G or K template matches, and the variant fitted on the 4700 to 6900 Å window reaches only 0.266. A template library without luminosity or metallicity matching to the sample cannot test a three-class $T_{\rm eff}$ classifier at this resolution, and we have not tried to repair it.


APPENDIX B: SUPPLEMENTARY TABLE AND FIGURES

This paper has been typeset from a TEX/LATEX file prepared by the author.

[ht]


Table B1. Ablation of the principal pairs by luminosity class and by distance to the nearest edge of the row's own T_{eff} bin (primary configuration). A dash marks an empty stratum.

Pair	Stratum	n	ΔA [95% CI]	Flips (l/g)	$\Delta\bar{P}_{\mathrm{true}}$
H Balmer, F	dwarfs	78	-0.859 [$-0.936, -0.782$]	67/0	-0.813
	giants	3	-0.333 [$-1.000, +0.000$]	1/0	-0.505
	≤ 150 K from boundary	34	-0.706 [$-0.853, -0.559$]	24/0	-0.667
	> 150 K from boundary	47	-0.936 [$-1.000, -0.851$]	44/0	-0.898
H Balmer, G	dwarfs	229	-0.921 [$-0.952, -0.886$]	211/0	-0.795
	giants	1	0.000 [$+0.000, +0.000$]	0/0	-0.305
	≤ 150 K from boundary	72	-0.806 [$-0.889, -0.708$]	58/0	-0.651
	> 150 K from boundary	158	-0.968 [$-0.994, -0.937$]	153/0	-0.857
H Balmer, K	dwarfs	38	$+0.211$ [$+0.079, +0.342$]	0/8	$+0.181$
	giants	107	0.000 [$+0.000, +0.000$]	0/0	$+0.010$
	≤ 150 K from boundary	24	$+0.292$ [$+0.125, +0.459$]	0/7	$+0.254$
	> 150 K from boundary	121	$+0.008$ [$+0.000, +0.025$]	0/1	$+0.016$
Mg B, G	dwarfs	229	-0.258 [$-0.314, -0.205$]	59/0	-0.262
	giants	1	0.000 [$+0.000, +0.000$]	0/0	0.000
	≤ 150 K from boundary	72	-0.444 [$-0.556, -0.333$]	32/0	-0.331
	> 150 K from boundary	158	-0.171 [$-0.228, -0.114$]	27/0	-0.229
Mg B, K	dwarfs	38	$+0.053$ [$-0.053, +0.158$]	1/3	$+0.047$
	giants	107	0.000 [$+0.000, +0.000$]	0/0	$+0.004$
	≤ 150 K from boundary	24	$+0.083$ [$-0.083, +0.250$]	1/3	$+0.069$
	> 150 K from boundary	121	0.000 [$+0.000, +0.000$]	0/0	$+0.005$
Na D, K	dwarfs	38	-0.026 [$-0.079, +0.000$]	1/0	-0.010
	giants	107	0.000 [$+0.000, +0.000$]	0/0	-0.001
	≤ 150 K from boundary	24	-0.042 [$-0.125, +0.000$]	1/0	-0.015
	> 150 K from boundary	121	0.000 [$+0.000, +0.000$]	0/0	-0.001
Ca I, K	dwarfs	38	0.000 [$+0.000, +0.000$]	0/0	-0.001
	giants	107	0.000 [$+0.000, +0.000$]	0/0	0.000
	≤ 150 K from boundary	24	0.000 [$+0.000, +0.000$]	0/0	-0.001
	> 150 K from boundary	121	0.000 [$+0.000, +0.000$]	0/0	0.000
Fe I/Cr I, K	dwarfs	38	-0.079 [$-0.184, +0.000$]	3/0	-0.049
	giants	107	0.000 [$+0.000, +0.000$]	0/0	-0.005
	≤ 150 K from boundary	24	-0.083 [$-0.208, +0.000$]	2/0	-0.051
	> 150 K from boundary	121	-0.008 [$-0.025, +0.000$]	1/0	-0.009



[ht]

Figure B1. Top: per-bin median normalised spectrum of the G class with the diagnostic-line positions marked and the inter-chip gap shaded. Bottom: normalised mean |SHAP| per class (F blue, G orange, K green) with the ten largest bins of each class marked. The ablation bars that an earlier version of this figure carried are Figure 1.



[ht]

Figure B2. Held-out test confusion matrix. Rows are the true class and columns the predicted class, in F–G–K order.